

OFFICE OF THE PRINCIPAL, HEMO PROVA BORBORA GIRLS' COLLEGE

P.O :Bengenakhowa, Dist : Golaghat – 785702, Assam, India.

Phone – 9435526875, Website- www.hpbgirlscollege.edu.in

Email- hpbgc1969@gmail.com

PART-B: FINANCIAL BID FORM-1

- NOTICE NO:
- NAME OF THE TENDERER:
.....
- FATHER'S NAME:
.....
- DATE OF BIRTH:.....
- DETAILS OF ADDRESS:
.....
- EMAIL:
- TELEPHONE/ MOBILE NO:
- PROJECT NAME: **RCC TYPE GIRLS' COMMON ROOM BUILDING (GROUND FLOOR) PART B**

- **RCC TYPE GIRLS' COMMON ROOM BUILDING (GROUND FLOOR) PART B
AT H.P.B GIRLS COLLEGE, GOLAGHAT, ASSAM**

Sl. No.	Item No.	Item Description	Unit	Qty	Rate Rs/Unit	Amount in Rs.
1		CHAPTER 1: FLOORING AND FLOOR FINISH				
	1.1.1	VITRIFIED TILES				
		A) ON FLOOR				
	1.1.2.1	Providing VITRIFIED floor tiles of approved quality of specified size, shape and thickness not less than 18mm on floors, skirtings, risers and treads of steps over 15 mm thick base of cement mortar in prop. 1:3 (1 cement : 3 coarse sand) including cutting where necessary finished with flush pointing with Fix-A-Tile (Choksey/Sika/Pedelite/Rouf) / white cement slurry mixed with approved pigment to match shade of tiles, mixed with approved pigment to match the shade of the tiles, complete at all levels as specified and directed. (Coloured pigment should be in conformity with colour of tiles and as approved and directed by the Department)				

		a) Normal range Somany/ Orient/Nitco /Varmora/VITA/ Marbitto/ Make				
		ii) Of size 600mmx600mm and above				
		Hall & Verandah	SQM	66.20		
	1.2	ANTISKID TILES				
	1.2.1	Providing Antiskid Tiles of approved quality size, shape not less than 8mm on floor, skirting over a cement mortar bed 15mm thick of 1:3 (1 cement: 3 coarse sand) approved make fix with Fix-A-Tile (Choksey/Sika/Pedelite/Rouf)/ white cement complete at all level as specified and directed.				
		(A) CERAMIC				
		i)Normal range (Sizes 300 mm x 300mm and above)				
		(a)Orient made: Galaxy Brown, Galaxy crema, Galaxy Pink, Galaxy Green, Pulsar Beige, Pulsar Blue, Pulsar Dove, Pulsar Pink, Burj Brown, Burj Green, Burj Slate				
		Toilet Area	SQM	11.50		
		Sub Total				
2		CH-2 : WOOD WORKS				
	2.1.1	Providing wood work in frame (chowkaths) of doors, windows,clerestory windows and other similar works wrought,framed and fixed in position in contact with C.C or brick masonry wall including supplying,fitting and fixing with M.S hold fast (40mm x 3mm x 250mm) as per design embedded in cement concrete block in proportion 1:2:4 and with two coats of kiricide oiling to the timber faces in contact with C.C and masonry as directed and specified				

		(b) With 1st class timber (Bonsum/ Sundi)	CUM	1.50		
	2.1.2	(a) Providing fitting and fixing 1st class local wood battened, ledged and braced door and window shutters including oxidised iron butt hinges (100mmx 58mmx1.90mm) 6 nos with necessary screws.				
		1) Door= 6 sqm	SQM.	6.00		
	2.2.3	Providing fitting and fixing 1st class local wood battened, framed and braced door and window shutters including oxidised iron butt hinges (100mm x58 mm x1.90 mm) 6 nos with necessary screws.				
		B)Using Gamari wood.				
		(ii) 35mm thick	SQM.	24.00		
		Sub Total				
3		CH-3 PVC, UPVC, FRP DOORS & DOOR FRAMES				
		P.V.C. DOORS & DOOR FRAMES				
	3.1	Providing, fitting and fixing PVC door frame of Duroplast make DPF-5060 make suitable for DPS-3720 made from extruded PVC multichamber hollow section having dimensions of 50mmx60mm (Toletance + 1mm). Horizontal and vertical sections shall be joined by steel screws after inserting M.S. tubular rectangular galvanised L-shaped brackets of size 100mmx100mm or plastic brackets of size 75mmx75mm with metred cut at the corners.				
	3.1.1	Hinge side of the frame shall be reinforced with M.S.Tubular section of size 40mmx20mm. The frame will be fixed to the column/ stiffner/ wall with the help of 3 nos 75mm long and 4mm dia steel screws and expandable fastners on each side of the door frame complete in all respects as sepcified and directed at all levels.				
		Toilet Door	Rm	14.85		

		Providing, fitting and fixing PVC Door shutters of Duroplast DPS 3720 make made from extruded PVC stiles and rails made from rigid PVC multicavity hollow chamber section of size 90mmx37mm (Tolerance+ 1mm). The corners of the stiles and rails shall be metred out and fixed to each other with the help of solid plastic L-shaped brackets or M.S. rectangular tubular galvanised two nos of size 200mmx100mm and 100mmx100mm at each corner by self tapping steel screws. PVC multicavity hollow section of size 105mmx37mm shall be fixed in the middle by aluminium cleat and steel screws as lock rail				
	3.2.1	The section frame shall then be filled with PVC panels of approved colour of size 100mmx20mm. Then two numbers of bright steel rods of 6mm diameter shall be inserted horizontally through stiles and panels with two numbers of checknuts and washers all complete as specified and directed at all levels. (Door fixtures and fittings to be measured and paid separately)				
			SQM	4.72		
		Sub Total				
4		CH: PAINTING				
	4.1.1	Finishing old/ new wall with water proofing weather coat smooth anti-fungal exterior painting of Apex brand of Asian Paints and of required shade after cleaning and clearing the surface etc. including scaffolding complete as directed at all levels (two coats)	SQM	193.34		
	4.1.2	Wall painting (two coats) with Plastic emulsion paint of approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) on new surface to give an even shade after thoroughly brushing the surfaces free from mortar droppings and other foreign matter and sand papered smooth.				
		(a).Plastic Emulsion Paint of approved brand and manufacture (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac)	SQM	444.50		

					Sub Total:	
					TOTAL (A)	
5		CHAPTER 6: MISCELLANEOUS WORKS- (SOR SWS)				
	6.2	SEPTIC TANK				
	6.2.1	Supplying and placing ferrocement septic tanks of rectangular shape in to pit with manhole cover with cleaning arrangement over single brick flat soling and 75mm 1:3:6 P.C.C. Baffle wall, inlet and outlet etc are provided at suitable points complete as directed.				
	(VII)	50 Users	each	1		
6		CHAPTER - 5: EXTERNAL WATER SUPPLY WORKS				
	5.4	WATER TANK				
	5.4.2	Supplying and placing plastic cylindrical vertical cloused top (PCVC) tank of Sintex / Polycon / Patton make over the staggig with manhole cover with locking and cleaning arrangement including providing pads of size as required for inlet and outlet pipes				
	(III)	1000 LIT CAPCITY				
		(a) Sintex make	each	1		
	5.1	Piping				

	5.1.1	Supplying fitting and fixing Pipes with all necessary fittings in exposed or in trenches including trenching and refilling the same etc complete as directed				
		C) CPVC pipe with CPVC fittings (Using SUPREME/ PRINCE/ SFMC/ FUSION brand pipe)				
		iii) 25mm (OD) diameter (internal water supply pipe)	Rm	34.5		
		vi) 50mm (OD) diameter(waste water pipe)	Rm	20.4		
		ix) 90mm (ID) diameter(soil pipe)	Rm	11.6		
		Sub Total:				
		CHAPTER - 3 : INTERNAL WATER SUPPLY WORKS (ORIGINAL)				
7	3.2	BIB COCK				
	(VI)	Sona brand				
		(i) Bib Cock (Code.No.RG-5015)	each		3	
	3.3	STOP COCK				
	3.3.2	Supplying fitting and fixing chrome plated (C.P.) stop-cock of approved brand and size as mentioned below as directed and specified.(G.I. & C.P pipes will be measured and paid separately)				
	(IV)	Sona brand				
		(a) 15mm dia Stop cock male-female /Angle stop cock	each		6	

	3.5	PILLAR COCK				
	3.5.1	Supplying and fitting fixing C.P. pillar cock of 15mm dia of approved brand as specified and directed.				
	(I)	SONA make(Light Type)	each	3		
	Sub Total:					
8		CHAPTER-1 : SANITARY WORKS (ORIGINAL)				
	1.5	PVC FLUSHING CISTERN				
		Supplying, fitting and fixing PVC flushing cistern with all internal fittings with CI brackets including fitting and fixing standard size CP flush pipe, union clamps etc. compete as directed and specified (pipes will be measured separately)				
		i) Parryware make(White)				
		(ii) Deluxe Single Flush (Cat. No. C8091/C8057)	each	3		
		WASH BASIN				
	1.13.2	Providing vitreous China wash basin with CI/MS brackets, C.P brass chain with plug,PVC waste pipe including painting of fittings and brackets, cutting and making good the walls wherever required. (Pillar cock, stop cocks, waste coupling are to be paid separately)				
		Basin (without pedestal)				
		(B) Hindware Make				

		(a) White				
		(i) Alto 510 x 400 (Cat. No.10091)	each	3		
		EUROPEAN TYPE WATER CLOSET				
	1.2	Providing fitting and fixing vitreous china pedestal type water closet (European type W.C pan 400mm high) with seat and lead ,CP brass hinges and rubber buffers , CI/MS brackets , 40 mm dia flush band with fittings including painting of fittings and brackets, required. (Flushing Cistern to be paid separately)				
		B) Hindware make				
		a) White				
		(i) Water closet Green (Cat No.20079) (inclusive of seat cover)	each	3		
		Sub Total:				
9		OTHERS/MISCELLANEOUS Like Towel Rail, Mirror, Connection Pipe, Ball Valve etc..	1	1	L/S	
		TOTAL :				
10	1. For Internal Electrification		1	L/S		
11	1. For External Electrification		1	L/S		
		So The Total Amount will be:(A)				
12	Add GST (@ 12% - 5% = 7%) of Total Amount (A)					
13	Taking 1% As Contigency (A)					

Certified that the above information is given by me and is true to the best of my knowledge and belief.

Signature with Seal

List of documents enclosed: